

**ITB #202012**  
**New Traffic Signal at Adams/Legge**  
**Questions & Answers**

**Updated 9/19/2020**

Q1. Do you have the price sheets in excel version that you could provide to bidders for use in preparing the bid?

A1. No, the City does not have that available.

Q2. Completion date for this project is 180 days after NTP. The poles and arms are 24 to 28 weeks lead time. When will the NTP start?

A2. As per Addendum #1, the completion date is being modified to 300 calendar days after the Notice to Proceed.

Q3. There is a note on the plans that says these plans are unfinished and not for construction. What if any changes will be made on the plans for construction?

A3. There are no anticipated changes to the plans. Any changes would be handled by an appropriate change order.

Q4. What does line item # 2 include? I didn't see anything in the project manual or on the plans.

A4. This item includes saw cutting, removing, and disposing of any concrete sidewalk or asphalt roadway needed to complete the work and for temporary restoration of these areas. The contractor can temporarily restore concrete sidewalks with stone backfill and restore asphalt areas with appropriate stone backfill and then cold-mix asphalt. At the conclusion of the contractor's work, the City will make permanent repairs to the concrete sidewalk and asphalt roadways.

Q5. Is there any DBE requirement for this project?

A5. No, there are no federal funds being utilized for this project.

Q6. Does the City have laydown the contractor can use for this project?

A6. No. The contractor shall be responsible for securing a laydown area.

Q7. Does the City have a disposal area site the contractor can use for this project?

A7. No. The contractor shall be responsible for disposing of any materials.

Q8. Any special permits the City is requiring for this project

A8. The contractor shall be responsible for obtaining an electric permit from the City. There will be no fee for this permit.

Q9. Will the City take care of calling the Power Company for the service or is this cost on the contractor?

- A9. The contractor shall be responsible for this and the costs shall be included in Bid Item #45, Electric Service.
- Q10. Signal plans note says pavement markings shall be installed but there is no pay item for pavement markings. Will these be added to the bid items or will the City install them?
- A10. The City will install the pavement markings when the contractor has completed their work.
- Q11. Will there be a line added to cover the removal of the light pole on the Northeast Quadrant per the plans. Will there be a line added to cover the removal of the light pole on the Northeast Quadrant per the plans
- A11. No. The City will coordinate with Shenandoah Valley Electric and they will remove this light pole.
- Q12. Drawings specify UPS cabinet mounted to right side of controller cabinet. Will you be adding a pay item for UPS cabinet?
- A12. Yes, a line item for this has been added – see revised Bid Form in Addendum #1.
- Q13. Will you be adding a pay item for the video detection camera cable Y cable (BNC to 2 wire)?
- A13. Yes, a line item for this has been added – see revised Bid Form in Addendum #1.
- Q14. For the radio will a line item be added for antenna cable/cat 5e?
- A14. No. The cost for this shall be included in Bid Item #58.
- Q15. The bid items and the signal plans for this project both indicate VDOT MP-3 poles, but the technical specification indicates 1994 AASHTO design build. Please clarify.
- A15. The technical specification shall govern. Please see clarifying notes on the revised Bid Form and revised Drawing provided in Addendum #1.
- Q16. What documents need to be submitted with the bid?
- A16. The Bid Form, Addendum Acknowledgement, Non-Collusion Affidavit, and Bid Bond need to be included when submitting the bid.